BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

Tender No: BBMP/EE/DD/TEN/01/13-14 Date: 04.07.2013 **ITEM NO: 04**

SCHEDULE-B

NAME OF WORK:Construction of RCC Drain at Kammagondanahalli Stephens School, in Ward no. 12, in Shettyhalli Sub-Division.

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **R SHIVARAM**		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	9
1	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	312.48	124.2	Rupees One Hundred Twenty Four and Twenty Paise Only	38810.02
2	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220 kgs, using 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregate @ 0.465cum machine mixed, concrete laid in layers not exceeding 15cms. Thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	39.06	3799.5	Rupees Three Thousand Seven Hundred Ninety Nine and Fifty Paise Only	148408.47
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs, with 20 mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS9103 1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase lintels retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour HOM of machinery, curing complete as per specifications.	Cum	94.40	4819.95	Rupees Four Thousand Eight Hundred Nineteen and Ninety Five Paise Only	455003.28

Signature of the Contractor

Executive Engineer

4	Pro ing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Qtls	56.64	6737.6	Rupees Six Thousand Seven Hundred Thirty Seven and Sixty Paise Only	381617.66
5	Providing and removing centering, shuttering, strutting, propping etc., for edges of slabs and breaks in floor, cills, plinth including cost of all materials, labour complete as per specification.	Sqm	868.00	520.64	Rupees Five Hundred Twenty and Sixty Four Paise Only	451915.52
6	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & Complete as per specfications.	Sqm	195.30	1472.0	Rupees One Thousand Four Hundred Seventy Two Only	287481.60
7	Disposal of debris to the final place of disposal with all lead , lift and as direction by the engineer in charge of the work, lead 10 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading. Complete as per specfications.	Cum	312.48	92.32	Rupees Ninety Two and Thirty Two Paise Only	28848.15
					Total	1792084.70
					Percentage	-8.00%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,